# Ekistica

#### Off Grid Electrification in Australia and the Pacific Region

Project Experiences and Lessons Learned

TRANSLATE. CREATE. DELIVER.

#### APEC EGNRET Workshop:

Off Grid Electrification Option for Remote Regions in APEC Economies 10<sup>th</sup> September 2018, Chang Mai, Thailand



Who is Ekistica

Off Grid Electrification
Electrification and energy services
Scale of electrification
Energy supply options
Structural barriers

Off Grid Electrification in Australia and the Pacific
Bushlight Program

- SETuP
- Cook Islands

## Who is Ekistica

- Engineering Consultancy, based in Alice Springs, Australia
- Wholly owned by Centre for Appropriate Technology (CfAT) and indigenous owned and managed NGO
- Provide engineering advice, design and implementation services.
- Clients include World Bank, ADB, local, state and national governments, NGO's and private enterprise
- Specialists in remote areas service delivery, renewable energy, power systems and water and sanitation
- Broad project experiencing in Australia and overseas including the Cook Islands, Fiji, Solomon Islands, New Guinea, Indonesia, Cambodia, India, Nepal and Kenya
- <u>https://www.ekistica.com.au</u>

EKISTICA.COM.AU



### **Off Grid Electrification**

The term **Off Grid Electrification** is a broad term encompassing a wide range of possibilities


#### **Definition**:

"The delivery of electrical energy services to persons, places and communities who do not otherwise have access to established centralized electricity networks"

The key term here is **energy service** 



### Electrification and Access to Energy Services



#### **Energy Services**

- Connection is not the same as access
- Aim is to deliver a meaningful energy service
- What is the Level of Energy Service
  - o Is it what end users need or want?
  - o Is it affordable?
  - o Can it be delivered

Important to define up front the energy service level that the electrification project/program aims to deliver as this

- Underpins the engagement with the end user, to manage expectations and set appropriate tariffs
- Informs the both the required scale of the power system(s) and the most suitable technology
- Allows for development of effective understanding of Capex/Opex and financing over the full project life cycle

### Scale of Off Grid Electrification

• The required energy service level informs the scale of the required Off Grid Electrification system

#### **Distributed Power Systems**

Solar Lights( 0-50W)



Solar Home Systems (50-500W)

W) Stand Alone Power Systems (0.5-10kW)



**Centralized Power Systems/ Microgrids** 

#### Small (10-1000kW)



EKISTICA.COM.AU

#### Medium (1-10MW)



Large (10-200MW)



### Identifying Best Energy Supply Options


- For remote areas the identifying the best options for electricity generation depend on the following factors
  - Energy service to be delivered
  - Required scale of power system
  - Available energy resources
  - Available technology
  - Accessibility of site (road, sea, seasonal impacts)
  - The nature of the load (load profile)
  - Power requirements (availability, reliability, quality etc)
  - Regulatory requirements
  - Capacity of individuals and organization to design, install, operate and maintain system
  - System finances. Needs to be understood and managed over the whole project life cycle



### **Energy Supply Options**

- Three main options include
  - Conventional generation (petrol, diesel and gas)
  - Renewable energy (solar PV, solar thermal, wind, hydro, biomass, geothermal)
  - Energy Storage System (ESS) (chemical batteries (BESS), pumped hydro, ultracapacitors etc)

System Scale	Typical Power Range	Typical Generation Options
Solar Lights/Charger	0 - 50 W	PV/BESS
Solar Home Systems (SHS)	50 – 500 W	PV/BESS
Stand Alone Power System (SPS)	0.5 - 10kW	PV/BESS/Hydro/Petrol/Diesel
Small Microgrids (Village)	10 – 1000 kW	PV/BESS/Hydro/Biomass/Wind/Diesel
Medium Microgrids (Town)	1 – 10 MW	PV/BESS/Hydro/Biomass/Wind/Diesel/Gas
Large Microgrids	10–200 MW	PV/BESS/Hydro/Biomass/Wind/Geothermal/Solar Thermal/Diesel/Gas




Finance

Supply Chain

#### Off Grid Electrification in Australia

- Large land mass (larger than Europe, similar to mainland USA and China)
- Relatively small population (25 Million in 2018) predominately clustered around east coast
- Many remote towns, communities, outstations, mines, cattle stations, tourist facilities
- Network/grid coverage is large but limited to areas of higher population density
- Long history with Off Grid Electrification
- Traditionally powered by diesel/gas.
- Shift to renewables and in remote areas this means solar PV



#### Map: Network Coverage




#### Map: Solar Irradiance



< 1100 1300 1500 1700 1900 2100 2300 > kWh/m

### **Bushlight Program**

- Federally funded program aimed at reducing reliance on diesel generation in remote indigenous communities in Central and Northern Australia
- Replacement of diesel generation with PV/BESS
- 155 new or replacement PV/BESS or PV/BESS/Diesel hybrids installed
- Ongoing O&M for over 250 off grid power systems
- Strong focus on
  - Meaningful community engagement
  - Capacity building (industry, government and community)
  - Quality, reliability and serviceability
- Project commenced in 2003 and was defunded in 2013



www.bushlight.org.au

### Capacity Building

. . .

#### **Community engagement**

WASHING	ENTERTAINMENT		CC	COOKING		HAIR CLIPPERS	
ULOTHES	OB	2 hours		8@)	TC		zo minutes per day
		10 hours	2		gas burner		HEATING
🔷 or 🐲		3 hours					
DEPENDS ON BATTERIES		3 hours	)	*			BULISER minintes per day
COOLING HOUS	E	FOOD CO	DOL	LIGHTS	S		CHRISTMAS LIGHTS
Bedroom 1				Bedroom 3	x ! hour		A Thomas per s
8 hours			0	Verandah 1)	(3 hour	C	KEY BOARD A I howr
Bedroom 2					ezhour /		per day
& 8 hours	1		0		x 12 hour x 2 hour		SEWING MACHINE
Bearcom 3 8 hours				ALL CONTRACTOR	x 6 hour		20 minutes per day
alestal ran			0			POWER	TOOLS
L a the				HA 100 A	hult	32	
on vorendeh		-			1	-	A CAL BUILDING COMP

G. P. B. B.

### Quality Hardware and Installation

Ē









ELECTROCARD METER




#### Lessons Learned

- Very successful program overall (was extended to India in 2009-2012)
- Critical elements of success included
  - o Effective community engagement and capacity building
  - Ensuring quality components and installation
  - Demand side management
  - Ongoing operation and maintenance
  - Commitment to ongoing funding for O&M
  - Building installer/maintainer/support agency capacity
- Must take the long view and plan and implement for system life cycle



#### The Solar Energy Transformation Program (SETuP)

- SETuP is funded by the Australian Government through the Australian Renewable Energy Agency (ARENA) and the Northern Territory Government owned utility Power and Water Corporation (PWC). Commenced 2016.
- SETuP delivering a wide-scale rollout of 10MW of solar systems across 25 remote Indigenous communities where they currently operated diesel power plants
- Aim is to reduce diesel consumption by through low penetration PV (15-20%). Typically 300 to 500kW PV per site
- One site (Daly River) also selected to host large PV/BESS plant. Includes 1MW PV array and 2MWh Lithium Ion BESS.










AN

#### **Project Outcomes**

- Program commenced 2016 and still be rolled out
- PV/BESS/Diesel system has reduced diesel consumption by over 60%
- PV/Diesel systems have reduced diesel consumption by ~ 15%. This could be higher but utility is very conservative with control system
- Payback period approximately 5-6 years
- Potential for future rollout (another 50 similar sites available)
- Expansion of PV/Diesel system to PV/BESS/Diesel
- Project delays due to climate
- Lightning protection systems important in these northern areas

#### The Cook Islands – Outer Islands Project

- GoCl project with funding from NZMFAT
- Aim to reduce reliance on diesel generation
- Installation of eight PV/BESS/Diesel systems
- Very remote islands/atolls population (100-500)
- Key design issues include
  - Reliability
  - Portability
  - Modularity
  - Hot, humid and salt air climate
  - Cyclones and storm surges
  - Include remote monitoring
- Project completed in 2015
- Second Phase Inner Islands underway





EKISTICA.COM.AU



#### Lessons Learned

- Very successful project to date (3 years)
- Most systems operating above 95% PV energy fraction
- Risk has cost. Requirement to work through cyclone season increased costs
- Land access can be a major problem
- Additional project costs in upgrading existing enabling infrastructure
- Governance issue remain a concern
  - Recommended tariff structures not adhered to
  - Long term maintenance program not locked in
  - Lack of capacity building impacts local ability to manage



#### THANKS FOR WATCHING

Desert Knowledge Precinct 90 Heath Road Alice Springs, NT 0870 T: 08 8959 6240 F: 08 8959 6111 E: enquiries@ekistica.com.au



EKISTICA.COM.AU